BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/OW/WORK_INDENT30471

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Maintenance of Electrical cremetorium building in hebbal in ward no. 7 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B M Muniraju	
				In Figures	In Words
1	120	KSRRB 300-1. Earthwork excavation and forming in embankment by manual means in rodinary soil(when earth is taken from bank cutting or from borrow pits) including breaking of clods, spreading to required line and level, forming and cost of all labour complete as per specifications..	cum	118.0	Rupees One Hundred Eighteen Only
2	37.5	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification	cum	5493.0	Rupees Five Thousand Four Hundred Ninety Three Only
3	25	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	cum	6141.0	Rupees Six Thousand One Hundred Forty One Only
4	60	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications.	Sqm	1030.0	Rupees One Thousand Thirty Only
5	100	Providing flooring with cement design concrete design concrete tiles of aproved colour designfor external flooring to the floor . The thickness of the tiles should be minimum of 10mmand should have compressive strength of M-52 confirming to IS 1237-1980 Specifications fixing in cement mortar 1:3and using reodixed colour to fill the joints btween the tiles etc., complete including the cost of material, labour, transporatation, all taxes charges etc., as per instruction of Engineer in charges, ultra tiles pebble beach grey colour (Data Rate) as approved by	Sqm	1437.0	Rupees One Thousand Four Hundred Thirty Seven Only
6	90	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.	Nos	411.0	Rupees Four Hundred Eleven Only
7	40.5	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications.	Sqm	30.0	Rupees Thirty Only
8	34	Providing and fixing Ornamental benches (Delhi benches) as per design, drawing specification and directions of Engineer in charge.	Sqm	8883.0	Rupees Eight Thousand Eight Hundred Eighty Three Only
9	120	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	cum	110.0	Rupees One Hundred Ten Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/07

19/07